

1 **Methods for preserving duration-intensity correlation on synthetically generated** 2 **water demand pulses**

3 Enrico Creaco¹, Stefano Alvisi², Raziye Farmani³, Lydia Vamvakeridou-Lyroudia⁴, Marco Franchini⁵,
4 Zoran Kapelan⁶, Dragan Savic⁷

6 **Abstract**

7 This paper proposes the application of three different methods for preserving the correlation between
8 duration and intensity of synthetically generated water demand pulses. The first two methods, i.e., the
9 Iman and Canover method and the Gaussian copula respectively, are derived from known statistical
10 approaches, though they had never been applied to the context of demand pulse generation. The third is a
11 novel methodology developed in this work and is a variation in the Gaussian copula approach. Poisson
12 models fitted with the methods are applied to reproduce the measured pulses in one household, with
13 parameters being obtained with the method of moments. Comparisons are made with another method
14 previously proposed in the scientific literature, showing that the three methods have similar effectiveness
15 and are applicable under more general conditions.

17 **Keywords:** Water demand, demand pulses, intensity, duration, correlation, Iman-Canover, Gaussian
18 copula

19

¹ College of Engineering, Mathematics and Physical Sciences, University of Exeter, North Park Road, Exeter EX4 4QF – UK.
Email: E.F.Creaco@exeter.ac.uk

² Dipartimento di Ingegneria, Università degli Studi di Ferrara, Via Saragat 1, 44100 Ferrara – Italy. Email:
stefano.alvisi@unife.it

³ College of Engineering, Mathematics and Physical Sciences, University of Exeter, North Park Road, Exeter EX4 4QF – UK.
Email: R.Farmani@exeter.ac.uk

⁴ College of Engineering, Mathematics and Physical Sciences, University of Exeter, North Park Road, Exeter EX4 4QF – UK.
Email: L.S.Vamvakeridou-Lyroudia@exeter.ac.uk

⁵ Dipartimento di Ingegneria, Università degli Studi di Ferrara, Via Saragat 1, 44100 Ferrara – Italy. Email:
marco.franchini@unife.it

⁶ College of Engineering, Mathematics and Physical Sciences, University of Exeter, North Park Road, Exeter EX4 4QF – UK.
Email: Z.Kapelan@exeter.ac.uk

⁷ College of Engineering, Mathematics and Physical Sciences, University of Exeter, North Park Road, Exeter EX4 4QF - UK.
Email: D.Savic@exeter.ac.uk

20 **Introduction**

21 In the last two decades, residential water demand generation has been extensively investigated. Various
22 models (Buchberger and Wu, 1995; Buchberger and Wells, 1996; Guercio et al., 2001; Alvisi et al., 2003;
23 Garcia et al., 2004; Buchberger et al., 2003; Alcocer et al., 2006; Blokker et al., 2010; Alcocer-Yamanaka
24 and Tzatchkov, 2012; Alvisi et al., 2014; Creaco et al., 2015) have been proposed to generate water
25 demand pulses at the scale of individual user with fine temporal resolution (down to 1 sec). In fact, this
26 modelling is useful in the framework of the “bottom-up” approach (Walski et al., 2003) for network
27 demand definition, since the generated pulses can be aggregated temporally and spatially to yield nodal
28 demands inside water distribution models. Unlike other demand generation models, which produce
29 demand values at prefixed time steps, pulse generation models generate the time arrival, duration and
30 intensity of each pulse. Therefore, the local flow field given by these models can also be used as an input
31 to water-quality models that require ultrafine temporal and spatial resolutions to predict the fate of
32 contaminants moving through municipal distribution systems (Buchberger and Wu, 1995).

33 Some of these models (Buchberger and Wu, 1995; Buchberger and Wells, 1996; Guercio et al., 2001;
34 Buchberger et al., 2003; Garcia et al., 2004; Alcocer et al., 2006; Creaco et al., 2015) use the Poisson
35 pulse model for the generation of pulse time arrivals, whereas pulse durations and intensities are
36 generated using suitable probability distributions. In most cases (Buchberger and Wu, 1995; Buchberger
37 and Wells, 1996; Guercio et al., 2001; Buchberger et al., 2003; Garcia et al., 2004; Alcocer et al., 2006),
38 pulse duration and intensity were considered to be independent random variables. However, Creaco et al.
39 (2015) have recently shown that a non-negligible positive correlation exists between the two variables.
40 The same authors then postulated that this has to be considered in order to obtain synthetic water demand
41 pulses that are more consistent in terms of overall daily water demand volumes, while respecting
42 statistical properties of measured demand pulses. In particular, the Authors’ method is based on the use of
43 a bivariate probability distribution (in particular, the bivariate normal distribution). However, researchers
44 may choose to represent pulse durations and intensities through marginal probability distributions that do
45 not provide for any bivariate distribution modelling. For example, this was previously done by Guercio et
46 al. (2001) and Garcia et al. (2004), who used the normal and exponential distributions and the Weibull

47 and exponential distributions respectively. Therefore, the issue of how correlation can be preserved in a
48 more general context, i.e. when a bivariate probability distribution does not exist, needs to be dealt with.

49 In this paper, three methods are described that can be applied to obtain correlated pulse intensities and
50 durations for any marginal distribution used to represent the two variables as independent random
51 variables.

52 In the following sections, first the methodologies are described, then they are applied to a literature case
53 study and a comparison with the method of Creaco et al. (2015) is also provided. Finally, results are
54 analysed and conclusions are drawn.

55

56 **Methodology**

57 Hereinafter, first the typical Poisson model with no correlation between pulse intensity and duration is
58 described. Then, the methods used to preserve correlation are presented, followed by the model
59 parameter estimation.

60

61 *Poisson model*

62 Time axis is sampled with a certain time resolution Δt . The probability $P(z)$ of having z generated pulses
63 in the time interval Δt that follows the generic time τ is described by the Poisson distribution (Buchberger
64 and Wu, 1995):

$$65 \quad P(z) = \frac{e^{-\lambda\Delta t} (\lambda\Delta t)^z}{z!} \quad \text{with } z = 0, 1, \dots \quad (1)$$

66 where rate parameter λ represents the expected number of “events” or “arrivals” that occur per unit time.

67 For each pulse generated, the associate duration T and intensity I are generated using suitable probability
68 distributions. As an example, the density functions of the beta and gamma distributions (Johnson and
69 Bhattacharyya, 1992) are provided in eqs. (2) and (3) respectively:

$$70 \quad f(x) = \frac{1}{B} \frac{\left(\frac{x - x_{\min}}{x_{\max} - x_{\min}} \right)^{\alpha-1}}{\left(1 - \frac{x - x_{\min}}{x_{\max} - x_{\min}} \right)^{\beta-1}} \quad (2)$$

$$71 \quad f(x) = \frac{x^{k-1} e^{-\frac{x}{\theta}}}{\theta^k \Gamma(k)} \quad (3)$$

72 where x is the random variable, equal to T or I , depending on which variable has to be generated; α and β
73 are the parameters of the beta distribution and $B=B(\alpha, \beta)$ is the beta function; k and θ are the parameters
74 of the gamma distribution and $\Gamma=\Gamma(k)$ is the gamma function. Whereas the gamma distribution is defined
75 on the interval $[0,+\infty[$, the beta distribution is defined on the interval $[x_{\min}, x_{\max}]$. Therefore, in order for
76 the latter to be used for the generation of either the duration or the intensity, the interval $[x_{\min}, x_{\max}]$ has to
77 be defined. In any case, the cumulative distribution function F that ranges from 0 to 1 can be obtained as
78 (Johnson and Bhattacharyya, 1992):

$$79 \quad F(x) = \int_0^x f(x) dx \quad (4)$$

80 After distribution parameters values have been fixed, values of the generic random variable can be
81 sampled by generating for F random numbers in the range $[0,1]$ and then deriving the corresponding
82 elements of x by inverting eq. (4).

83 If a Poisson model is used with constant parameter values to generate water demand pulses for a certain
84 time duration, a sequence of n pulses, each of which featuring its own time arrival τ_i , duration T_i and
85 intensity I_i , would be obtained, as shown in Table 1.

86 Variables T and I , as they appear in columns 2 and 3 of Table 1, are independent random variables; the
87 corresponding correlation matrix \mathbf{C} (see eq. 5) should thus feature an expected value of ρ , Pearson
88 correlation coefficient out of the diagonal, equal to 0.

$$89 \quad \mathbf{C} = \begin{pmatrix} 1 & \rho \\ \rho & 1 \end{pmatrix} \quad (5)$$

90

91 *Preserving correlation*

92 Method 1: Iman and Canover (IC) (1982)

93 The Iman and Canover (1982) procedure is made up of two steps. In step 1, variables T and I are
94 generated as independent random variables, as is described above. This results in matrix \mathbf{X} , which is in

95 fact made up of columns 2 and 3 of Table 1; the corresponding correlation matrix \mathbf{C} is given by eq. (5).
 96 Step 2 is then applied to find a new pairing for these variables, which enables the desired/observed
 97 correlation ρ_{ep} value to be preserved between the variables.

98 In step 2, the following matrix operations are performed, which first entail constructing matrix \mathbf{C}_p related
 99 to the desired/observed correlation ρ_{ep} to be preserved:

$$100 \quad \mathbf{C}_p = \begin{pmatrix} 1 & \rho_{ep} \\ \rho_{ep} & 1 \end{pmatrix} \quad (6)$$

101 Then, matrices \mathbf{L} and \mathbf{L}_p can be obtained as lower triangular matrices from the Cholesky decomposition
 102 (Press et al., 1990) of matrices \mathbf{C} and \mathbf{C}_p respectively.

103 The new matrix \mathbf{X}_1 , which features a correlation matrix equal to \mathbf{C}_p in eq. (6), has to be calculated as:

$$104 \quad \mathbf{X}_1 = \mathbf{X} \cdot (\mathbf{L}_p \cdot \mathbf{L}^{-1})^T \quad (7)$$

105 The elements of each column of matrix \mathbf{X} have to be reordered in order to have the same sorting as the
 106 elements of the corresponding column of matrix \mathbf{X}_1 , thus producing the matrix \mathbf{X}_2 . In this manner, the
 107 matrices \mathbf{X}_2 and \mathbf{X}_1 will have the same rank correlation matrix, and, consequently, similar (Pearson)
 108 correlation matrices. Since the application of step 2 simply modifies the sorting of the T and I values and
 109 does not change the values themselves, it preserves the exact form of the marginal distributions on these
 110 variables, as it comes from step 1.

111

112 Method 2: Gaussian copula

113 Unlike method 1 that is applied to pulse durations and intensities that have already been generated,
 114 method 2 precedes the generation. A further difference lies in the fact that method 2 does not entail
 115 matrix operations.

116 Method 2 is known as the method of the Gaussian copula (Nelsen, 1999). It is based on generating n
 117 couples of auxiliary random variables y_1 and y_2 with average values equal to 0 and standard deviations
 118 equal to 1 through the bivariate normal distribution (eqs. 8 and 9):

$$119 \quad f(y_1, y_2) = \frac{1}{\sqrt{(2\pi)^2 |\Sigma|}} e^{\left[-\frac{1}{2(1-\rho)} (y_1^2 + y_2^2 - 2\rho y_1 y_2) \right]}, \quad (8)$$

$$\Sigma = \begin{pmatrix} 1 & \dot{\rho} \\ \dot{\rho} & 1 \end{pmatrix} \quad (9)$$

where $\dot{\rho}$ represents correlation between y_1 and y_2 .

For each of the n values generated for y_1 , the value F_1 of the cumulative probability of the marginal distribution can be calculated. In a similar way, for each of the n values generated for y_2 , the value F_2 of the cumulative probability of the marginal distribution can also be calculated.

The n values of F_1 and F_2 can be used to sample the probability distributions chosen for pulse durations and intensities (eq. 4) and then to obtain n couples of T and I . As a result of correlation $\dot{\rho}$ imposed between y_1 and y_2 , a certain degree of correlation is also imposed on T and I . In particular, the resulting correlation between T and I is a monotonous function of $\dot{\rho}$. Iterative methods can then be applied in order to determine the suitable value of $\dot{\rho}$ that yields the expected correlation ρ_{ep} to be preserved between T and I .

Method 3

Method 3 is a modified version of method 2. Similar to the original method, it does not require matrix operations and is based on the use of the bivariate normal distribution (eqs. 8 and 9). However, following from method 1, it is applied after a preliminary first step, in which n uncorrelated couples of T and I are generated.

Then, n couples of y_1 and y_2 with correlation equal to $\dot{\rho}$ are also generated. As in method 2, the corresponding values of F_1 and F_2 can be obtained. T and I can be reordered using the same sorting as F_1 and F_2 respectively. As a result of correlation $\dot{\rho}$ imposed between y_1 and y_2 , a certain degree of correlation is also imposed on T and I . Iterative methods can be applied in order to determine the suitable value of $\dot{\rho}$ that yields the expected correlation ρ_{ep} to be preserved between T and I .

Parameter estimation

The set of parameters of a Poisson model for pulse generation, in which T and I are generated as independent random variables, by using either the beta (eq. 2) or the gamma distribution (eq. 3), or using any kind of 2 parameter probability distribution, is 5: one parameter (λ) for pulse arrival and two

147 parameters for either of T or I . If correlation between T and I needs to be accounted for, the number of
148 parameter increases to 6 and correlation ρ_{ep} is the sixth parameter of the model.

149 As it was done by some authors (Alvisi et al., 2003; Buchberger et al., 2003; Creaco et al., 2015), the
150 generic day of the month can be subdivided into a certain number of time slots (e.g., 12 bihourly) for
151 parameter estimation. Robust models can then be obtained by allowing pulse arrival-related parameter λ
152 to take on a different value in each daily time slot. Each of the other parameters (in this case, the
153 parameters related to T and I and correlation ρ_{ep}), instead, is allowed to take on a single value valid for all
154 the time slots.

155 For estimating the parameters of the Poisson model, the method of the moments (Hall, 2004) was used,
156 which consists in setting the values of the parameters equal to the corresponding values in the measured
157 pulses.

158

159 **Applications**

160 *Case studies*

161 By making calculations on data collected during an experimental campaign in some households in
162 Milford, Buchberger et al. (2003) were able to reconstruct, with one second time step resolution, the
163 water demand pulses which were taking place in these households in the period from April to October
164 1997. The data made available by the Authors concern pulse duration T , intensity I and volume $V=T \cdot I$.

165 As case study in this work, the indoor water demand pulses recorded in one of the households, i.e.
166 household 2, in the month of April were selected. This case study has already been chosen by Creaco et
167 al. (2015) on the basis of the regularity of the daily water consumption. The basic statistical parameters
168 of measured water consumption variables z , T , I , V , D and ρ are reported in Table 2.

169 The modelling framework of this paper is aimed at investigating the extent to which the methods
170 described in this paper for preserving correlation lend themselves to being used inside Poisson models.

171 Overall, four Poisson models were constructed and compared with two benchmark Poisson models,
172 hereinafter indicated as models A and B and drawn from the work of Creaco et al. (2015). In particular,
173 model A features pulse durations and intensities being generated through the bivariate lognormal

174 distribution. This enables correlation to be obtained between the two variables in this model. Model B
175 differs from model A in that pulse durations and intensities are generated as independent (uncorrelated)
176 variables by making use of the lognormal distribution. The four models constructed in this work are
177 models C-1, C-2, C-3, and D. Models C-1, C-2 and C-3 differ from model A in the way correlation is
178 preserved. In fact, unlike model A, these models feature adoption of one of the three methods described
179 hereinabove (methods 1, 2 and 3 respectively). Model D differs from model C-3 in the generation of
180 pulse durations and intensities, which take place through the beta (eq. 2) and gamma (eq. 3) distributions
181 respectively, instead of the lognormal distribution.

182 Overall, applications consisted in 3 phases for each test:

183 phase 1 – parameter assessment;

184 phase 2 – generation of synthetic water demand pulses;

185 phase 3 – analysis of the results of the models and comparison with the observed data.

186

187 *Results*

188 Phase 1

189 The results of phase 1 for models C-1, C-2, C-3 and D are reported in Table 4 and 5. The results for
190 models A and B, instead, can be found in the work of Creaco et al. (2015). For the analysis of these
191 tables, it has to be recalled that only λ is parametrized in 12 daily time slots; the other parameters,
192 instead, are assigned a single daily value. The data reported in Tables 4 and 5, related to models C-1, C-2,
193 C-3 and D, were obtained by applying the method of the moments (Hall, 2004). As was expected, Table
194 4 shows that the λ values obtained in the various time slots are identical for models C-1, C-2, C-3 and D.
195 This is due to the fact that all these models deal with pulse arrival generation in the same way and they
196 only differ in the way pulse intensities and durations are generated. In model D, in which the beta
197 distribution is used to generate pulse durations, the interval $[x_{\min}, x_{\max}]$ was set to $[0, 850]$ following
198 analysis of the experimental pulses.

199

200 Phase 2

201 The models calibrated in phase 1 were then applied in order to create synthetic demand pulses for one
202 month (i.e. 30 days - April) for each test. In order to account for the influence of the random seed, each
203 generation was repeated 100 times.

204 In each of the models which use one of the methods described hereinabove to preserve correlation
205 (models C-1, C-2, C-3 and D), the method was applied once at the end of each of the 100 monthly
206 generations of pulses.

207 As an example, Figure 1 shows the single realization of the simulated total demand for a typical day at
208 the scale of 1 sec, obtained by using model C. As expected, the figure shows a higher concentration of
209 the pulses in the morning and in the late afternoon, when the household occupants usually get up and get
210 back home after work. Very few pulses are instead generated at nighttime. This is a direct consequence
211 of the λ values in the bihourly time slots.

212

213 Phase 3

214 A first analysis was made concerning the basic statistical parameters of water consumption variables z , T ,
215 I , V and ρ derived from the pulses generated by models A-D, in comparison with those of the measured
216 pulses (see Table 1). This table shows that all the models reproduce well $\text{mean}(z)$, $\text{mean}(T)$, $\text{var}(T)$,
217 $\text{mean}(I)$ and $\text{var}(I)$. This is a direct consequence of the goodness of the method of the moments for
218 parameter calibration.

219 Correlation ρ is only preserved in those models which are constructed considering the correlation, i.e.
220 models A, C-1, C-2, C-3 and D. As expected, model B leads to $\rho=0$, since the pulse duration and
221 intensity are generated independently from each other in this model. Similar considerations can be made
222 with regard to $\text{cov}(T,I)$. With regard to ρ , the analysis of Table 1 proves that the methods adopted in
223 models C-1, C-2, C-3 and D have similar effects to the use of the bivariate distribution in model A. The
224 advantage for these methods of being also applicable in the cases (see model D) where no bivariate
225 distribution is available, that is when T and I are represented by two different kinds of marginal
226 probability distributions, must also be highlighted. As for pulse volume V , only the models that consider

227 correlation, i.e. A, C-1, C-2, C-3 and D, are those that return consistent values of mean(V), i.e. values of
228 mean(V) close to the value mean(V)=9.45 L of the measured pulses. As a consequence of this, the same
229 models provide consistent values of mean (D), i.e. values of mean(D) close to the value of mean(D)=442
230 L/day associated with the measured pulses.

231 Another test was then carried out to compare the synthetic water demand pulses generated by means of
232 the models with the measured water demand pulses in terms of overall daily water demand volume D . In
233 particular, the total synthetic water demand volume D was calculated for each day in the generic one
234 month long pulse generation of each test. Then, the cumulative frequency curve was constructed
235 reporting, for each value of D , the Weibull cumulative frequency F of days in the month that feature a
236 value of the overall daily water demand volume lower than or equal to D . Since each model application
237 comprises 100 one-month long pulse generations, a band of synthetic cumulative frequencies was then
238 obtained for each test. For each test, the band upper envelope (BUE), lower envelope (BLE) and mean
239 value (BMV) of the 100 cumulative frequency curves were determined for all the models. The
240 cumulative frequency of the measured daily water demand volume (ECF) was also calculated.

241 The graphs in Figure 2 report BUE, BLE and BMV obtained using the various models as well as ECF.
242 Analysis of the graphs shows that, as already highlighted by Creaco et al. (2015), the BMV obtained with
243 model A (model that takes into account the mutual dependence of pulse intensity and duration by means
244 of the bivariate distribution) follows ECF much more closely than that obtained with model B (model
245 that neglects the mutual dependence of pulse intensity and duration). Furthermore, all the data points of
246 ECF lie inside the band of cumulative frequency obtained with model A. Only a few ECF data points,
247 instead, are found inside the band of cumulative frequency obtained with model B. This attests to the
248 better capability of model A to generate water demand pulses that are consistent with the observed
249 demand pulses in terms of overall daily water demand volume. Figure 2 also shows that models C-1, C-2
250 and C-3, which use the methods described in this paper to preserve correlation, have an almost identical
251 performance to model A. The change in the distributions used to represent the pulse durations and
252 intensities does not affect results significantly (see results of model D with method 3). This is due to the

253 fact that, in the case study considered, the beta and gamma probability distributions fit the measured
254 pulse durations and intensities in a similar way to the lognormal distributions used in method A.

255

256 **Conclusions**

257 This paper presented the application of three different methods that can be used to preserve correlation
258 between duration and intensity of water demand pulses. Whereas the first two methods are derived from
259 the known statistical approaches, the third was newly developed in this work. Applications showed that
260 the three methods yield similar results to those previously reported by Creaco et al. (2015) with the
261 advantage of being applicable with any marginal distributions to represent the duration and the intensity.
262 Subsequently, the following consideration can be made as far as the preservation of duration/intensity
263 correlation in synthetically generated pulses is concerned. In order to preserve this correlation, a bivariate
264 probability distribution has to be chosen to represent pulse durations and intensities, as was shown by
265 Creaco et al. (2015), when the marginal distributions chosen to represent these two variables can be
266 inserted in the framework of such modelling. If the latter condition does not hold, as it is the case with
267 the probability distributions chosen by some authors (e.g., Guercio et al., 2001; Garcia et al., 2004), one
268 of the three methods described in this paper can be profitably applied if correlation needs to be preserved.
269 Though the three methods have similar effectiveness, methods 1, based on the Iman-Canover (1982)
270 method, and method 3, novel variation in the Gaussian Copula (Nelsen, 1999), may turn out to be more
271 attractive for engineers. In fact, they can be easily implemented downstream of the standard methods for
272 generating independent pulse durations and intensities, in order to impose the correlation by post-
273 processing the results of the latter.

274 After the work of Creaco et al. (2015) showed that pulse generation models fitted with duration/intensity
275 correlation have advantages in comparison with traditional models and after this work has shown how
276 correlation can be obtained in a more general way, future work will be dedicated model parameter
277 assessment on the basis of smart meter readings. Compared to the current parameterization, which is
278 based on the method of the moments and stringently requires knowledge of real pulse features, the new

279 parameterization will significantly extend the applicability of the pulse generation models fitted with
280 duration/intensity correlation.

281

282 **Acknowledgements**

283 The authors thank Prof. S.G. Buchberger for providing the data demand for the Milford households. This
284 study was carried out as part of the ongoing projects: (i) “iWIDGET” (Grant Agreement No 318272),
285 which is funded by the European Commission within the 7th Framework Programme, (ii) the ongoing
286 PRIN 2012 project “Tools and procedures for an advanced and sustainable management of water
287 distribution systems”, n. 20127PKJ4X, funded by MIUR, and (iii) under the framework of Terra&Acqua
288 Tech Laboratory, Axis I activity 1.1 of the POR FESR 2007–2013, project funded by the Emilia-
289 Romagna Regional Council (Italy) ([http://fesr.regione.emiliaromagna.it/allegati/comunicazione/la-](http://fesr.regione.emiliaromagna.it/allegati/comunicazione/la-brochure-dei-tecnopoli)
290 [brochure-dei-tecnopoli](http://fesr.regione.emiliaromagna.it/allegati/comunicazione/la-brochure-dei-tecnopoli)).

291

292 **References**

- 293 Alcocer-Yamanaka, V.H., Tzatchkov, V., and Buchberger, S.G., 2006. Instantaneous Water Demand
294 Parameter Estimation from Coarse Meter Readings. In: Proceedings of the Water Distribution Systems
295 Analysis Symposium 2006, pp. 1-14.
- 296 Alcocer-Yamanaka, V.H., and Tzatchkov, V.G., 2012. Modeling of Drinking Water Distribution
297 Networks Using Stochastic Demand. *Water Resources Management*, 26, 1779-1792.
- 298 Alvisi, S., Franchini, M., and Marinelli, A., 2003. A stochastic model for representing drinking water
299 demand at residential level. *Water Resources Management*, 17 (3), 197–222.
- 300 Alvisi, S., Ansaloni, N., Franchini, M. 2014. Generation of synthetic water demand time series at
301 different temporal and spatial aggregation levels. *Urban Water Journal*, 11 (4), 297-310.
- 302 Blokker, E.J.M., Vreeburg, J.H.G., and van Dijk, J.C., 2010. Simulating residential water demand with a
303 stochastic enduse model. *Journal of Water Resources Planning and Management*, 136 (1), 375–382.
- 304 Buchberger, S.G., Carter, J.T., Lee, Y.H., and Schade, T.G., 2003. Random Demands, Travel Times and
305 Water Quality in Dead-ends, prepared for American Water Works Association Research Foundation,
306 AwwaRF Report No. 294, 2003, 470 pages.
- 307 Buchberger, S.G., and Wells, G.J., 1996. Intensity, duration and frequency of residential water demands.
308 *Journal of Water Resources Planning and Management*, 122 (1), 11–19.
- 309 Buchberger, S.G., and Wu, L., 1995. Model for instantaneous residential water demands. *Journal of*
310 *Hydraulic Engineering*, 121 (3), 232–246.
- 311 Creaco, E. , Farmani, R., and Kapelan, Z., Vamvakeridou-Lyroudia, L., Savic, D., 2015. Considering the
312 mutual dependence of pulse duration and intensity in models for generating residential water demand.
313 *Journal of Water Resources Planning and Management*, doi: 10.1061/(ASCE)WR.1943-5452.0000557.
- 314 Garcia, V.J., Garcia-Bartual, R., Cabrera, E., Arregui, F., and Garcia-Serra, J. 2004. Stochastic model to
315 evaluate residential water demands. *Journal of Water Resources Planning and Management*, 130 (5),
316 386–394.

317 Guercio, R., Magini, R., and Pallavicini, I., 2001. Instantaneous residential water demand as stochastic
318 point process. In: Water resources management, C. A. Brebbia et al. eds., WIT Press, Southampton,
319 U.K., 129-138.

320 Hall, A.R., 2004. Generalized Method of Moments. Advanced Texts in Econometrics, OUP Oxford,
321 ISBN: 0198775202, 9780198775201.

322 Iman, R.L., and Conover, W.J., 1982. A distribution-free approach to inducing rank correlation among
323 input variables. *Communication in Statistics*, 11, 311–334.

324 Johnson, R.A. and Bhattacharyya, G.K., 1992. *Statistics: Principles and Methods*. 2nd Edition. Wiley,
325 1992.

326 Nelsen, R.B., 1999. *An Introduction to Copulas*. Springer, New York, ISBN 0-387-98623-5.

327 Press, W.H., Flannery, B.P., Teukolsky, S.A., and Vetterling, W.T., 1990. *Numerical recipes: the art of*
328 *scientific computing*. New York: Cambridge University Press.

329 Walski M., Chase D., Savic D., Grayman W., Beckwith S. and Koelle E. (2003). *Advanced water*
330 *distribution modelling and management*. Waterbury, CT: Haestad Press.

331

Table 1. Arrival time τ , duration T and intensity I of the pulses generated by the Poisson model.

| τ (s) | T (s) | I (L/s) |
|--------------|-----------|-----------|
| τ_1 | T_1 | I_1 |
| τ_2 | T_2 | I_2 |
| ... | ... | ... |
| τ_i | T_i | I_i |
| ... | ... | ... |
| τ_{n-1} | T_{n-1} | I_{n-1} |
| τ_n | T_n | I_n |

335

Table 2. Basic statistical parameters of water consumption variables z , T , I , V , D and ρ derived from

336

the measured pulses and from the pulses generated by the models.

| pulse type | mean (z) [s ⁻¹] | mean (T) [sec] | var (T) [sec ²] | mean (I) [L/s] | var (I) [L ² /s ²] | mean (V) [L] | mean (D) [L/day] | cov (I,T) [L ²] | ρ [-] |
|-------------------|--|---------------------------------------|--|---------------------------------------|--|-------------------------------------|---|--|---------------------------------|
| measured | 0.00054 | 56 | 12743 | 0.106 | 0.00742 | 9.45 | 442 | 3.50 | 0.36 |
| model A | 0.00054 | 56 | 11822 | 0.106 | 0.00730 | 9.39 | 438 | 3.48 | 0.37 |
| model B | 0.00054 | 56 | 12321 | 0.106 | 0.00737 | 5.95 | 278 | 0.03 | 0.00 |
| model C-1 | 0.00054 | 56 | 12321 | 0.106 | 0.00737 | 9.26 | 431 | 3.34 | 0.35 |
| model C-2 | 0.00054 | 56 | 12049 | 0.105 | 0.00712 | 9.17 | 427 | 3.27 | 0.35 |
| model C-3 | 0.00054 | 56 | 12321 | 0.106 | 0.00737 | 9.27 | 432 | 3.36 | 0.35 |
| model D | 0.00054 | 56 | 12723 | 0.106 | 0.00744 | 9.44 | 440 | 3.50 | 0.36 |

337

Table 3. Features of the models used in this work.

| | distribution for duration | distribution for intensity | parameter estimation method | correlation method |
|----------------|----------------------------------|-----------------------------------|------------------------------------|---------------------------|
| model A | bivariate lognormal | bivariate lognormal | moments | Creaco et al. (2015) |
| model B | lognormal | lognormal | moments | no correlation |
| model C-1 | lognormal | lognormal | moments | method 1 |
| model C-2 | lognormal | lognormal | moments | method 2 |
| model C-3 | lognormal | lognormal | moments | method 3 |
| model D | beta | gamma | moments | method 3 |

340 Table 4. Calibrated values of λ for the various time slots, for models C-1, C-2 and C-3, D.

| models | slot 0h-2h | slot 2h-4h | slot 4h-6h | slot 6h-8h | slot 8h-10h | slot 10h-12h | slot 12h-14h | slot 14h-16h | slot 16h-18h | slot 18h-20h | slot 20h-22h | slot 22h-24h |
|-----------------|---------------|---------------|---------------|---------------|----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|
| C-1,C-2, C-3 | 0.000065 | 0.000028 | 0.001056 | 0.000991 | 0.000579 | 0.000356 | 0.000130 | 0.000333 | 0.001023 | 0.001032 | 0.000745 | 0.000157 |
| D | 0.000065 | 0.000028 | 0.001056 | 0.000991 | 0.000579 | 0.000356 | 0.000130 | 0.000333 | 0.001023 | 0.001032 | 0.000745 | 0.000157 |

341


342 Table 5. Calibrated values of daily parameters for models C-1, C-2 and C-3, D.

| parameters for C-1,C-2,C-3 | values | parameters for D | values |
|----------------------------|--------|------------------|--------|
| μ_{nT} | 3.22 | α | 0.17 |
| σ_{nT} | 1.27 | β | 2.33 |
| μ_{nI} | -2.50 | θ | 0.07 |
| σ_{nI} | 0.71 | κ | 1.51 |
| ρ_{ep} | 0.36 | ρ_{ep} | 0.36 |

343

344


Figures



345

346 Figure 1. Model C - single realization of the simulated total demand for a typical day at the scale of 1 sec.

347



348

349 Figure. 2. Upper (BUE) and lower (BLE) envelopes (grey lines) and mean value (BMV) (black line) of
 350 the band of Weibull cumulative frequencies F of daily water demand D produced by models A, B, C-1,
 351 C-2, C-3 and D, in comparison with the daily water demand cumulative frequency calculated starting
 352 from the measured data (ECF) (dots).